

TENDER NO: UBDCORP/Q/001/2026.

DIKLANKAN: 28/04/2026 [SELASA]

TARIKH TUTUP: 12/05/2026 [SELASA] JAM 11:30 PAGI

DOCUMENT FEE: \$20.00

IMPORTANT

The official PDF /tender form will be send via email once UBDCorp Official receipt issued and send to vendors/supplier for confirmation of payment received.

Mode of payment REFER IN UBD WEBSITE

Please take note that the document fee for each of the new and extended quotations will be BND \$20.00 each.

IMPORTANT NOTE: Please ensure that you provide the correct details when making the payment. Please email proof of the payment to office.ubdcorp@ubd.edu.bn

REF: UBDCORP/Q/001/2026

TITLE: RENOVATION WORKS FOR TOILET FACILITIES AT THE CORE

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	<u>GF- Male Toilet</u>				
1.1	Hacking and removal of existing wall tiles including disposal				
1.2	Hacking and removal of existing floor tiles including disposal				
1.3	Supply and lay new 300mm x 600mm ceramic wall tiles.				
1.4	Supply and lay new 300mm x 600mm non-slip ceramic floor tiles.				
	<u>GF-Female Toilet</u>				
1.5	Hacking and removal of existing wall tiles including disposal				
1.6	Hacking and removal of existing floor tiles including disposal				
1.7	Supply and lay new 300mm x 600mm ceramic wall tiles.				
1.8	Supply and lay new 300mm x 600mm non-slip ceramic floor tiles.				
	<u>GF- Disabled Toilet</u>				
1.9	Hacking and removal of existing wall tiles including disposal				
1.10	Hacking and removal of existing floor tiles including disposal				
1.11	Supply and lay new 300mm x 600mm ceramic wall tiles.				
1.12	Supply and lay new 300mm x 600mm non-slip ceramic floor tiles.				
2	<u>Mirror</u>				
	Supply and installation of 6mm thick clear float glass mirror with polished edges, securely fixed with concealed stainless-steel brackets or clips, complete with necessary backing board and silicone sealant.				
2.1	GF-Male Toilet -3000mm x 800mm	1	No		
2.2	GF-Female Toilet- 1850mm x 800mm	1	No		
2.3	GF-Disabled Toilet 900mm x 800mm	1	No		
CARRY FORWARD					

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
3	<u>Dismantling of Existing WC & Disposal</u> Carefully dismantling and removing existing water closet (WC) complete with cistern, seat cover, flush mechanism, connection fittings and accessories; including disconnection of water supply and waste pipe, making safe, loading, carting away and proper disposal off site at approved dumping area. All labour, tools, transport and incidentals included.				
3.1	GF-Male Toilet	2	Nos		
3.2	GF Female Toilet	1	No		
3.3	GF- Disabled Toilet	1	No		
4	<u>Supply & Install Water Closet (WC)</u> Supply, deliver and install new water closet (WC) complete with ceramic WC pan, cistern (chose-coupled or concealed type as specified), seat cover, flush mechanism, fixing accessories and all necessary fittings; including connection to existing water supply and soil pipe, testing, adjustment, commissioning and making good.				
4.1	GF-Male Toilet	2	Nos		
4.2	GF- Female Toilet	1	No		
4.3	GF-Disabled Toilet	1	No		
5	<u>Existing Art Basin - Dismantle & Reinstall</u> Carefully dismantle existing art basin including basin bowl, waste outlet, bottle trap, flexible hose, angle valve, mixer tap (if any), brackets and accessories; disconnect plumbing services, temporarily remove and protect; reinstall to original position after completion of renovation works, including refixing, alignment, reconnection to water supply and waste pipe, sealing, testing and commissioning.				
5.1	GF-Male Toilet	3	Nos		
5.2	GF-Female Toilet	2	Nos		
5.3	GF-Disabled Toilet	1	No		

6	<p><u>Supply & Floor Trap</u></p> <p>Supply, deliver and install new floor trap complete with grating, map body, removable cover, water seal and all necessary fittings; including connection to existing waste pipe, setting in position, alignment, sealing, testing for leakage and making good to surrounding finishes.</p>				
6.1	GF-Male Toilet	6	Nos		
6.2	GF-Female Toilet	5	Nos		
6.3	GF-Disabled Toilet	1	No		